

BRUHAT BANGLORE MAHANAGARA PALIKE



DASARAHALLI-ZONE

T.DASARAHALLI-SUB-DIVISION.

*Name of Work: Removal of Debris & Disilting of Drains in
Bagalagunte Ward No.14*

Estimate Cost :-10.00 Lakhs

BRUHAT BANGALORE MAHANAGARA PALIKE

DASARAHALLI ZONE

Name of Work :- Removal of Debris & Disilting of Drains in Bagalagunte rd No.14

		Est. Cost Rs				10.00	Lakhs	
Description of Item	Unit	No	L	B	D	Qty	Rate	Amount
Removing B.S. slab of drain and stacking with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work..(PWD SR 2016-17, Page No.25, Item No. 5.32)								
	Sqm	1	110.00	0.90		99.00		
		1	90.00	0.90		81.00		
		1	100.00	0.90		90.00		
		1	120.00	0.90		108.00		
Basic Rate	62.00					378.00	66.96	25311.00
Area Weightage 8%	4.96	3.72					65.72	
Total	66.96							
Excavation and removal of silt and silt mix with sand in slushy condition from final bed including disposing of the same in spoil bank or on canal embankment in layers as directed etc., complete with an initial lead upto 50m (MISR Page No.118, Item No. 51)								
Removing Road side debries	Cum	12	62.00	0.45	0.40	133.92		
Ramaiah Layout		9	90.00	0.45	0.30	109.35		
Sarga Layout		10	85.00	0.45	0.45	172.13		
Ideshwra Layout		8	80.00	0.45	0.40	115.20		
MH Layout		9	60.00	0.45	0.45	109.35		
Arloskar Layout		9	120.00	0.45	0.45	218.70		
Andarya Layout		5	110.00	0.45	0.45	111.38		
Andavana Layout		8	100.00	0.45	0.45	162.00		
Anjunatha Nagara		8	95.00	0.45	0.45	153.90		
Bagalagunte cross roads		12	106.00	0.45	0.45	257.58		
MI Layout Cross roads		7	136.00	0.45	0.45	192.78		
Chheshwaraiah Layout		11	105.00	0.45	0.45	233.89		
Subvaneshwari Nagara C/R		15	102.00	0.45	0.45	309.83		
Chappangi ramaiah Layout		9	80.00	0.45	0.45	145.80		
Gayalakshmi Layout		8	80.00	0.45	0.45	129.60		
Sheshadri Layout		9	100.00	0.45	0.45	182.25		
Fence colony		6	99.00	0.45	0.45	120.29		
Chok Nagara		9	90.00	0.45	0.45	164.03		
Chp Factory Layout		4	95.00	0.45	0.45	76.95		
						3098.90	214.74	665458.00

212.60

Description of Item	Unit	No	L	B	D	Qty	Rate	Amount
Basic rate	107.00							
Add area weightage 8%	8.56	6.42						
Total	115.56	113.42						
and upto 5 km	68.80							
and upto 9 km (4*5.76)	23.04							
al per cum	7.34							
Total	214.74							
3. Affixing stone slabs of drains and pointing in CM 1:3 etc complete Page No. 25/ n No.5.33/ PWD SR 2016-17								
	Qty Vide Item No 1					378.00	82.08	31026.00
					Sqm.		80.56	
Basic Rate	76.00							
Area Weightage 8%	6.08	4.52						
Total	82.08	80.56						
4. B. Excavator on hire basis including JCB Operator with Helper to carryout the ks on emergency as per the direction of Engineer-in-charge of the work (PWD 2016-17, P-XXXXVI, It.No.23)								
Emergency days	Days					26.00	6720.00	174720.00
5. Tractor 40 HP on hire basis including Tractor Driver with Helper to carryout the ks on emergency as per the direction of Engineer-in-charge of the work (PWD 2016-17, P-XXXXVI, It.No.19)								
Emergency days		4	17			68.00	1520.00	103360.00
6. Miscellaneous and Unforeseen Charges								
								7800
								125.00
							Total	1000000.00
(Rupees. Ten Lakhs Only)								

CERTIFICATE:-

1. Work spot has been inspected and the work is found to be necessary
2. Estimate is prepared as per the PW,P & IWTD -SR-2016-17
3. Provision made in estimate are adequate and essential.
4. This area comes under BBMP limits.

Assistant Engineer
Ward-14

Assistant Executive Engineer
T. Dasarahalli Sub-Division
B.B.M.P

Executive Engineer
Dasarahalli Division
B.B.M.P. Bangalore.

ನಂ. EE/PS/48/16-ನಿರ್ದೇಶ : 30.12.16

ದಾ. Ten lakhs only

ಅಂದಾಜು ಪಟ್ಟಿಗೆ ಆಧಾರವಾಗಿ ಮಂಡಿಸಿ ನೀಡಿದೆ

ಕಾರ್ಯದ ಅಭಿಯಂತರರು
ಬಿ.ಬಿ.ಎಂ.ಪಿ.ದಾಸರಹಳ್ಳಿ ವಿಭಾಗ
ದಾಸರಹಳ್ಳಿ, ವಲಯ, ಬೆಂಗಳೂರು.


ನಂ. EE/PS/48/16-ನಿರ್ದೇಶ : 30.12.16

ದಾ. Ten lakhs only

ಗಳ ಅಂದಾಜು ಪಟ್ಟಿಗೆ ಆಧಾರವಾಗಿ ಮಂಡಿಸಿ ನೀಡಿದೆ

ಕಾರ್ಯದ ಅಭಿಯಂತರರು
ಬಿ.ಬಿ.ಎಂ.ಪಿ.ದಾಸರಹಳ್ಳಿ ವಿಭಾಗ
ದಾಸರಹಳ್ಳಿ, ವಲಯ, ಬೆಂಗಳೂರು.

LEAD CHART FOR TRANSPORTING SILT FROM WORK SPOT TO DUMPING YARD



Lead chart indicating of
U. NO. 14 & 15 together with
together with Mallasandra Dumping
Site having av. lead distance of 4.00km.

(Signature)
Assist. Engineer
Ward no. 14 & 15


(Signature)
Assist. Executive Engineer
T. Dasarahalli Sub Division
BBMP

(Signature)
Executive Engineer
Dasarahalli Division-1
BBMP

BRUHATH BANGALORE MAHANAGAR PALIKE


Dasarahalli Zone - T.Dasarahalli Sub-division

Ward No. 14 - Bagalakunte



Legend

- | | |
|--|--|
| <ul style="list-style-type: none"> Streets Drain RMP-2015 Proposed Road Roads to be Widened Railway Line Power & Pipeline Water Bodies Ward Boundary Land Use Valley Sensitive Zone | <ul style="list-style-type: none"> Land Marks Choultry & Convention Hall Shopping Complex School, College & Institution Government Office Hospital Industries Market Apartment & Building Locality Park and Playground, Park Overhead Tank Church Mosque Temple |
|--|--|



Mapped By :



SKYGROUP & CURIPe

#53, 3rd Cross, Central Excise Layout;

Vijayanagar, Bangalore: 560040

Mob.no: +91-9880435939

web: www.skygroup.co.in